

SCDAV SCHOOL AT NOIDA - ESTIMATED COST OF PAINTING WORKS AS/DSR & MARKET RATES

S. No	Description of Item	Unit	Quantity	Rate	Amount	Whether DSR 2018 or Market Rates
	A. FINISHING WORKS					
1	Plastic Emulsion Paint, one or more coat only, on old surface, of Asian / Dulux	Sqm	1400.00			
2	Satin Enamel Paint on Class Room walls - of Asian / Dulux	Sqm	300			
3	Synthetic Enamel Paint of Asian / Dulux on old surfaces	Sqm	1050			
4	Old work white wash of Dehradun Lime.	Sqm	11600			
5	Oil Bound Distemper - Old work 2 coats, of Asian or Dulux.	Sqm	8900			
6	Lacquer polish on doors	Sqm	285			
a)	Lacquer polish on door frames/ Display Board	Rm	285			
7	Finishing the exterior surface with Textured exterior paint of required shade on old surface (one or more coats@ 1.82 ltr/10 sqm	Sqm	111			
8	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade (Weathercoat)	Sq. Mtr	150			
	Old work (Two or more coats applied @ 1.43 ltr/ 10 sqm)	Sqm	150			
9	Primer putty with scapping	Sqm	As required			
10	Duette Designer Paint	Sqm	112			
	GRAND TOTAL AMOUNT OF 'A'					

K.K. Chadha, Architect

